

1 010144

15.185.12202.0000

Docket No. D-07,749

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Completed 3-58
NE NE NE, SEC. 10, T 21 S, R 14 W/B
4950 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Lease Name Shepard "B" Well # 4 SWD

Operator: Murfin Drilling Company
Name & Address 250 North Water, Suite 300
Wichita, KS 67202

County Stafford 122.68
Well Total Depth 3775 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8" feet 260

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company License Number 6033
Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 10:40 am Day: 9 Month: June Year: 19 86

Plugging proposal received from Bill Brown

(company name) Murfin (phone) 316-267-3241

were: 5 1/2" at 3700' Open Hole from 3700-3775' DV at 850' with Black Magic
1 1/2" tubing parted at 360' - can still pump down well.

1st plug pump 200 sx cement down 5 1/2"

2nd plug pump 100 sx cement down 8 5/8"

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 11:15 am Day: 9 Month: June Year: 19 86

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 200 sx cement (3 sx hulls mixed with
cement) down 5 1/2" - got circulation - Maximum pressure 200 psi and shut in 0

2nd plug tied onto 8 5/8" and pumped 150 sx cement down 8 5/8" - Maximum pressure 400 psi
and shut in 275 psi.

Remarks: No recovery. Used Halcolite by Hallibutton.
(If additional description is necessary, use back of this form.)

Observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION
WICHITA, KANSAS

6-16-1986

JUN 16 1986

Signed [Signature]
(TECHNICIAN)

INVOICED

DATE JUN 18 1986

INV. NO. 14153

JUL 24 1986