

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185- 22,010.0000

SE SE NW , Sec. 15 , T 21 S, R 14 (W)

2310 feet from N/S section line

2310 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6393

Lease Name Ratzlaff "C" Well # 1

Operator: Brougher Oil, Inc.
Name & P. O. Drawer 1367
Address Great Bend, KS 67530

County Stafford

Well Total Depth 3755 feet 122.0f

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 356

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Mohawk Drilling, Inc. License Number 6394

Address P. O. Box 1362, Great Bend, KS 67530

Company to plug at: Hour: Day: Month: Year: 19

VERBAL PLUGGING ORDERS GIVEN TO Bud Biter

(company name) Mohawk (phone) 316-586-3317

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 3737' with 50 sx cement

2nd plug at 840' with 50 sx cement

3rd plug at 405' with 50 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement.

7th plug to circulate mouse hole with 10 sx cement Signed *Alyse Wiley* (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11:15 AM Day: 11 Month: 6 Year: 1984

ACTUAL PLUGGING REPORT 1st plug at 3737' with 50 sx cement, 2nd plug at 840' with 50 sx cement, 3rd plug at 405' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Hall.

RECEIVED
STATE CORPORATION COMMISSION
JUN 18 1984
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (/ did not) observe this plugging.

INVOICED

DATE 6-29-84

INV. NO. 2197

6-11

Signed *Alyse Wiley* (TECHNICIAN)