

120245

MAR 31 1989
API NUMBER 15-185-20,912

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SE NW, SEC. 15, T 21 S, R. 14 W
3630 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8318

Lease Name Ratzlaff A Well # 2

Operator: Carroll Oil
Name & Address: Box 1987
Great Bend, KS 67530

County Stafford 121.13

Well Total Depth 3727 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 368

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 31 Month: 3 Year: 19 89

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 5 1/2" at 3725' PBTD 3715' Perfs at 3695-3700'

1st plug sand back to 3645' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 110 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
APR 4 1989

4-4-1989

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations ended by Agent?: All Part _____ None _____

Operations Completed Hour: 11 a.m. Day: 31 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3645' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 350 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 150 lbs. hulls and 110 sx cement.

Pumping pressure 0-250 psi and shut in 0 psi, not on vacuum.

Cedar Hills flowed approximately 1/2" stream while pulling casing.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2003' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVESTIGATOR observe this plugging.

Signed Duane Rankin (TECHNICIAN)

DATE 4-18-89

INV. NO. 24324