

288 R

1 120244

MAR 31 1989

API NUMBER 15-185-20,609.0000

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NE NW, SEC. 15, T 21 S, R. 14 W/E

4290 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8318

Loase Name Ratzlaff A Well # 1

Operator: Carroll Oil

County Stafford 121.55

Name & Address

Box 1987

Well Total Depth 3740 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 386

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 11 a.m. Day: 31 Month: 3 Year: 19 89

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-938-2457

were: 5 1/2" at 3739' Perfs at 3685-90' TOC 3100'

1st plug sand back to 3635' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 1000 lbs. hulls and 200 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
APR 4 1989

4-4-1989

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations supervised by Agent?: All Part _____ None _____

Operations Completed: Hour: 1 p.m. Day: 31 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug hole bridged at 2532', dumped 5 sx cement on bridge with bailer,

2nd plug pumped into 8 5/8" surface casing with 200 lbs. hulls, 130 sx cement with 500 lbs. hulls mixed with cement.

Pumping pressure 0-1300 psi and shut in 1000 psi.

Casing pulled into at 360'.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 360' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (Name) observe this plugging.

DATE 4-18-89

Signed Duane Rankin (TECHNICIAN)

INV. NO. 24325