

1 050819

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-20,928.0000

NE NE SW, SEC. 15, T 21 S, R 14 ^{W XX}
2310 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5428
Operator: Graves Drilling Co., Inc.
Name & Address 910 Union Center
Wichita, KS 67202

Lease Name Krampe Well # 1
County Stafford 121.94
Well Total Depth 3752 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 240

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:00 am Day: 12 Month: June Year: 19 86

Plugging proposal received from Ronnie Hoover

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 3751' PBTD 3752' Perfs at 3607-3612' w/2spf

1st plug sand back to 3550' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:45 am Day: 12 Month: June Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3550' and dumped 4 sx cement on top of

sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement,

10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 125 sx cement.

Maximum pressure 400 psi and shut in 50 psi

Remarks: Recovered 1500' 4 1/2" casing. Used 60/40 ROBERTSON 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

(If observed) observe this plugging.

DATE JUN 18 1986

INV. NO. 14130

Signed Richard W. Lacey Jr.
(TECHNICIAN)