

1052302

TO: STATE CORPORATION COMMISSION

1-7

API NUMBER ⁰⁰⁰¹ 15-185-01152-~~0000~~
NW SE SW SEC. 15, T 21 S, R 14 W

CONSERVATION DIVISION - PLUGGING SECTION 990 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 990 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME KRAMPE A WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY STAFFORD 123.0%

OPERATOR LICENSE # 5921 (EXPIRED) WELL TOTAL DEPTH 3785 FEET

OPERATOR: JON M. CARROLL PRODUCTION CSG: SIZE 4 1/2" @ 3784' WITH 150 SX

NAME AND BOX 1987 SURFACE CASING: SIZE 8 5/8" @ 270' WITH SX

ADDRESS GREAT BEND, KS 67530

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR DS&W WELL SERVICING LICENSE NUMBER 6901

ADDRESS PO BOX 231 CLAFLIN, KS 67525

COMPANY TO PLUG AT: HOUR: 10:00 AM DAY: 06 MONTH: 01 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM KENT STRUBE

(COMPANY NAME) DS&W (PHONE) 316-587-3361

WERE: PERFS AT 3748-50 3519-3524

1ST PLUG SAND TO 3470' AND 4 SX CEMENT. 2ND PLUG AT 840' WITH 50 SX CEMENT.

3RD PLUG AT 300' WITH 50 SX CEMENT.

4TH PLUG AT 40-0' WITH 10SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE DURRANT

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 5:00 PM DAY: 07 MONTH: 01 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG SAND TO 3450' AND 4 SX CEMENT. SPOTTED PLUG THROUGH CASING. 2ND PLUG AT 840'

WITH 10 SX GEL - 50 SX CEMENT. 3RD PLUG AT 300' WITH 50 SX CEMENT. 4TH PLUG AT 40'

ON 1-7-99 WELL BROKE OUT FLOWING WATER AND FLOWED OUT TOP CEMENT. PUMPED DOWN 8 5/8" WITH

200# HULLS MIXED IN 100 SX COMMON CEMENT 2% CC. MAXIMUM PRESSURE 1000 PSIG SHUT IN

AT 750 PSIG.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1870' OF 4 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Richard W. Lacy (TECHNICIAN) FORM CP-2/3

RECEIVED
JAN 12 1999
1-12-1999

1-15-99
60544