

To: 1 041152
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License / 30081

Operator: Anshutz Oil
Name:
Address: Rt. 1, Box 46
Seward, KS 67577

API NUMBER 15- 185-21,843 - 0000
NW NW SE, SEC. 15, T 21 S, R 14 W/E
2310 feet from S section line
2310 feet from E section line
Lease Name Krampe Well # 1-15
County Stafford
Well Total Depth 3800 123.50 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 305

Abandoned Oil Well Gas Well Input Well SMD Well O&A

Other well as hereinafter indicated

Plugging Contractor O.G.H. Oil Co. License Number 3154

Address Rt. 1, Box 87, Wilson, KS 67490

Company to plug at: Hour: 9:30 a.m. Day: 1 Month: 3 Year: 19 96

Plugging proposal received from Larry Dolechek

(company name) O.G.H. Oil Co. (phone) 913-658-3528

were: 5 1/2" at 3799' w/125 sx cement, Perfs at 3730-34'

1st plug sand back to 3680' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10 a.m. Day: 1 Month: 3 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 3680' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 600 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1875' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form)

Observe this plugging.

INVOICED
DATE MAR 13 1996
INV. NO. 45033

Signed *Steve Pfeifer*
(TECHNICIAN)

RECEIVED
KANSAS CORP COMPT
MAR - 7 AM '96