

1052422

TO: STATE CORPORATION COMMISSION

API NUMBER 15-185-20548-00-00
NW NW NE SEC. 15, T 21 S, R 14 W

CONSERVATION DIVISION - PLUGGING SECTION 4950 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2310 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME ANSCHUTZ WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY STAFFORD 120.48

OPERATOR LICENSE # 30081

WELL TOTAL DEPTH 3707 FEET

OPERATOR: ANSCHUTZ OIL COMPANY PRODUCTION CSG: SIZE 4 1/2" @ 3703' WITH 150 SX

NAME AND PO BOX 274 SURFACE CASING: SIZE 8 5/8" @ 334' WITH SX

ADDRESS ELLSWORTH, KS 67439-0274

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ANSCHUTZ OIL COMPANY LICENSE NUMBER 30081

ADDRESS SAME AS ABOVE

COMPANY TO PLUG AT: HOUR: 10:30 AM DAY: 21 MONTH: 08 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM LARRY DOLECHEK

(COMPANY NAME) ANSCHUTZ OIL COMPANY (PHONE) 785-658-3528

WERE:

SAND TO 3625' & 4 SX CEMENT. 1ST PLUG AT 850' WITH 50 SX CEMENT & 10 SX GEL.

2ND PLUG AT 350' WITH 50 SX CEMENT. 3RD PLUG AT 0-40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY SCOTT ALBERG

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 1:15 PM DAY: 21 MONTH: 08 YEAR: 2000

ACTUAL PLUGGING REPORT

SANDED TO 3600' & 4 SX CEMENT WITH DUMP BAILER. SPOTTED PLUGS THROUGH TUBING.

1ST PLUG AT 850' WITH 10 SX GEL & 50 SX CEMENT. 2ND PLUG AT 350' WITH 50 SX CEMENT.

3RD PLUG AT 62' WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1875' OF 4 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED
DATE 8/30/00 SIGNED Richard G. Lacey
(TECHNICIAN)
2001060572

FORM CP-2/3

RECEIVED
STATE CORPORATION COMMISSION

AUG 28 2000

CONSERVATION DIVISION
Wichita, Kansas