

1 030434

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 093-20,816 - 0000

C NW SE, SEC. 21, T 21 S, R 35 (W) K

1980 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5131

Lease Name Wingate Well # 1

Operator: Thunderbird Drilling, Inc.

County Kearny 162.83

Name & Address P. O. Box 18407

Well Total Depth 5010 feet

Wichita, KS 67230

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 388

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Thunderbird Drilling, Inc. License Number 5131

Address P. O. Box 18407, Wichita, KS 67230

Company to plug at: Hour: 1:00 pm Day: 7 Month: June Year: 19 85

Plugging proposal received from Maynard Weber

(company name) Thunderbird (phone) 316-685-1441

were: 4 1/2" at 4585' Perfs at: 4458-4464' DV tool at 2488-circulated with 535 sx cement

Squeeze well with 3 sx hulls, 40 sx cement, 25 sx gel, 1 sack hulls and 100 sx cement.

Plugging Proposal Received by Don G. Ubel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 10:15 am Day: 30 Month: July Year: 1985

ACTUAL PLUGGING REPORT Squeezed well with 3 sx hulls, 40 sx cement, 25 sx gel, 1 sack hulls and 4 sx cement. (Pressured up with only 4 sx cement at surface).

Cleaned out hole to 1100' and filled with 85 sx cement to surface.

Remarks: No recovery. Used 50/50 Pozmix 6% gel 3% cc by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE AUG 06 1985
INV. NO. 9343

STATE CORPORATION COMMISSION
Signed: Steve Plumont (TECHNICIAN)

AUG 2 1985 8-2-1985