

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-039-00519-00-00
Spot: NESESE Sec/Twnshp/Rge: 2-1S-27W
990 feet from S Section Line, 4950 feet from W Section Line
Lease Name: WARNER UNIT Well #: 107
County: DECATUR Total Vertical Depth: 3475 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>31569</u>	PROD	5.5	3475		650 SX
Op Name: <u>BACH, JASON DBA BACH OIL PRODUC</u>	SURF	8.625	322		250 SX
Address: <u>PO BOX 723</u> <u>ALMA, NE 68920</u>					

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/14/2017 12:30 PM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Rcvd. from: DALE FERLAND Company: BACH, JASON DBA BACH OIL PRO Phone: (785) 302-1435

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/800 # hulls.
DV Tool at 1953' w/400 sx cement.
Production perforations: 3240' - 3402'

Plugging Proposal Received By: DARREL DIPMAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/14/2017 4:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3220' and pumped 115 sx cement w/350 # hulls. Pulled tubing to 2250' and pumped 115 sx cement w/200 # hulls. Pulled tubing to 1150' and pumped 120 sx cement w/150 # hulls to circulate cement to surface. Closed backside valve. Pumped 20 sx cement to circulate 8 5/8" x 5 1/2" annulus to surface. Pulled all tubing. Topped off 5 1/2" casing with 20 sx cement.

GPS: 39.99042N -100.31032W

Perfs:

Top	Bot	Thru	Comments
3394	3402		
3362	3367		
3323	3339		
3240	3402		

INVOICED
OCT - 3 2017

Remarks: GLOBAL CEMENTING TICKET # 3079

Plugged through: TBG

District: 04

Signed _____

Pat Bedore
(TECHNICIAN)

CM

KCC WICHITA

SEP 28 2017

RECEIVED

SEP 21 2017