

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-02681-00-00
Spot: NWSWNW Sec/Twnshp/Rge: 25-20S-9W
3630 feet from S Section Line, 4950 feet from E Section Line
Lease Name: TOBIAS Well #: 15
County: RICE Total Vertical Depth: 3362 feet

Operator License No.: 34318

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3283		
CIBP	5.5	3336		
PROD	5.5	3357		100 SX
SURF	8.625	203		190 SX

Op Name: BEREXCO LLC

Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/11/2017 11:30 AM

Plug Co. License No.: 34318

Plug Co. Name: BEREXCO LLC

Proposal Rcvd. from: DENNIS KIRMER

Company: BERESCO LLC

Phone: (316) 772-6449

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER

Witness Type: PARTIAL

Date/Time Plugging Completed: 09/12/2017 2:15 PM

KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, TAG PREVIOUSLY SET CIBP @ 3270'. PERFORATE AT 1125', 725' AND 253'. RUN TUBING TO 3220' AND PUMP 50 SX'S COMMON WITH 3% CC AND 100 #'S COTTON HULLS. PULL TUBING TO 2840' AND PUMP GEL SPACER (17 SX'S) TO 1135'. PULL TUBING TO 1125' AND PUMP 35 SX'S COMMON WITH 3% CC. PULL TUBING OUT AND WAIT 1.5 HOURS. ATTEMPT TO TAG CEMENT - COULD NOT. WAITED UNTIL NEXT DAY, TAGGED CEMENT AT 800'. RUN TUBING TO 725' AND PUMPED 35 X'S COMMON WITH 3% CC, PULLED TUBING TO 253' AND CIRCULATED CEMENT TO SURFACE. PULLED TUBING OUT AND TOPPED OFF. USED 250 SX'S TOTAL.

Perfs:

Top	Bot	Thru	Comments
3353	3360		CSG
3298	3303		CSG
3270	3274		CSG
3262	3265		CSG
3224	3244		CSG

INVOICED
OCT - 3 2017

Remarks: PERF TECH #13725. QUALITY OIL WELL CEMENT #402 AND 404. DENIED TA WELL DUE TO HFLD.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)