

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-21323-00-00
Spot: SWNE Sec/Twnshp/Rge: 1-16S-30W
4321 feet from S Section Line, 1016 feet from E Section Line
Lease Name: RUSH Well #: 1-1
County: LANE Total Vertical Depth: 4440 feet

Operator License No.: 30104
Op Name: CAMBRON, PAUL L.
Address: 118 N PENN PO BOX 384
NESS CITY, KS 67560

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| PC | | 2070 | | WITH 200 SX CMT |
| PROD | 5.5 | 4437 | 0 | WITH 150 SX CMT |
| SURF | 8.625 | 383 | | WITH 175 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/11/2017 9:00 AM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Revd. from: HAL HOSS Company: CHEYENNE WELL SERVICE, INC. Phone: (785) 798-2282

Proposed Plugging Method: SQUEEZE PERFS WITH 30 SX CMT & 100# HULLS. RTIH TO 2100' WITH 30 SX CMT. PLUG AT 1260' WITH CMT TO 0'. CHECK BACKSIDE WITH CMT TO 300#.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/11/2017 5:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 30 SX CMT WITH 200# HULLS AT 4325'. 1ST PLUG AT 2100' WITH 30 SX CMT. 2ND PLUG AT 1260' WITH 130 SX CMT. RAN OUT OF CMT. NO CMT TO SURFACE. AFTER 4 HOURS RAN TBG TO 1260'. CIRCULATE CMT TO SURFACE WITH 200 SX CMT. TOOH WITH TBG & TOP OFF CASING WITH 25 SX CMT. STAYED FULL.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4360 | 4365 | | |

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed *Ken Jehlik*
(TECHNICIAN)

RECEIVED
SEP 18 2017
KCC DODGE CITY

INVOICED
OCT 11 2017