

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-04882-00-01
Spot: NWSESW Sec/Twnshp/Rge: 32-15S-12W
1050 feet from S Section Line, 3648 feet from E Section Line
Lease Name: NEY (HILGENBERG) Well #: 3
County: RUSSELL Total Vertical Depth: 3283 feet

Operator License No.: 6569
Op Name: CARMEN SCHMITT, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3329		0 SX
SURF	8.625	227		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/21/2017 9:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: CURTIS HITSCHMANN Company: CARMEN SCHMITT, INC. DBA Phone: (620) 793-2540

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 12 sx gel and 400 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/21/2017 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1450', 780' and 225'. Ran tubing to 3150' and pumped 12 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 1450' and pumped 70 sx cement w/200 # hulls. Pulled tubing to 780' and pumped 50 sx cement. Pulled tubing to 250'. Circulated cement to surface with 30 sx cement. Pulled tubing and topped off with 5 sx cement. Tied to surface casing and pressured up to 300 psi. Would not take cement.

GPS: 38.69959 -098.68427

Perfs:

INVOICED
OCT 11 2017

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

KCC WICHITA

SEP 28 2017

RECEIVED

SEP 07 2017

Form CP-2/3