

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-039-21242-00-00
Spot: NESEENENW Sec/Twnshp/Rge: 15-1S-29W
935 feet from N Section Line, 2460 feet from W Section Line
Lease Name: EAGLE 1 MOORE Well #: 1
County: DECATUR Total Vertical Depth: 4175 feet

Operator License No.: 9860
Op Name: CASTLE RESOURCES, INC.
Address: PO BOX 583
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	207		175 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/13/2017 12:00 AM
Plug Co. License No.: 34743 Plug Co. Name: WHITE KNIGHT DRILLING LLC
Proposal Rcvd. from: TERRY AUSTIN Company: WHITE KNIGHT DRILLING LLC Phone: (785) 303-8005

Proposed Plugging Method: Ordered 290 sx 60/40 pozmix - 4% gel cement with 1/4# flo-seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER Witness Type: NONE
Date/Time Plugging Completed: 09/13/2017 8:00 AM KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

Perfs:

1st plug @4137 w/50 sx
2nd plug @2280 w/50 sx
3rd plug @1530 w/100 sx
4th plug @260 w/50 sx
5th plug @40 w/10 sx

Rathole 30 sx

Remarks: GLOBAL

Plugged through: DP

INVOICED
OCT 11 2017

District: 04

Signed Ed Schumacher
(TECHNICIAN)

CM

KCC WICHITA

SEP 28 2017

RECEIVED

SEP 21 2017