

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-179-21174-00-00  
Spot: SEWNENESE Sec/Twnshp/Rge: 23-6S-26W  
2235 feet from S Section Line, 945 feet from E Section Line  
Lease Name: SLIPKE Well #: 1-23  
County: SHERIDAN Total Vertical Depth: 3922 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>35300</u>	PROD	4.5	3920		150 SX
Op Name: <u>COACHMAN ENERGY OPERATING CO</u>	SURF	8.625	348		225 SX
Address: <u>1125 17TH ST., SUITE 410</u> <u>DENVER, CO 80202</u>					

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/01/2017 8:30 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: BOB PLANTE Company: COACHMAN ENERGY OPERATING Phone: (720) 476-3678

Proposed Plugging Method: Ordered 250 sx 60/40 pozmix 4% gel cement, 400 # gel and 300 # hulls.  
8 5/8" surface casing set at 348' w/225 sx cement.  
4 1/2" production casing set at 3920' w/150 sx cement.  
TD 3922'. Port Collar set at 2204' w/450 sx cement.  
Perforations: 3842' - 3860'.  
Operator elected to plug top down and re-designed plugging plan.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/05/2017 12:00 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Top down plug. Connected to 4 1/2" production casing and pumped 60 sx cement w/300 # hulls followed by 400 # gel and 175 sx cement. 4 1/2" casing on vacuum. Cement dropped to 700' from surface. Connected to 8 5/8" surface casing and pumped 15 sx cement. Pressured to 250 psi.  
09/05/2017 - Ordered 200 sx 60/40 pozmix 4% gel cement. Global Oilfield Services filled 4 1/2" production casing with 50 sx cement. Cement ticket # 3129  
GPS: 39.51519N -100.18398W

Perfs:

Top	Bot	Thru	Comments
3857	3860		
3842	3844		

Remarks: GLOBAL OILFIELD SERVICES LLC TICKET # 3126

Plugged through: CSG

INVOICED  
OCT 11 7387

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

CM

KCC WICHITA

SEP 12 2017

SEP 28 2017

RECEIVED