

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-153-20885-00-00
Spot: NESWNWNE Sec/Twnshp/Rge: 19-1S-31W
725 feet from N Section Line, 2000 feet from E Section Line
Lease Name: SATTLER Well #: 1-19
County: RAWLINS Total Vertical Depth: 4225 feet

Operator License No.: 35300
Op Name: COACHMAN ENERGY OPERATING CO
Address: 1125 17TH ST., SUITE 410
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4221		115 SX
SURF	8.625	330		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/30/2017 10:00 AM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Revd. from: JUSTIN HAMLIN Company: COACHMAN ENERGY OPERATING Phone: (620) 544-5981

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 800 # gel and 500 # hulls.
PC at 2766' w/350 sx cement.
Production perforations: 4071' - 4075'

Plugging Proposal Received By: DARREL DIPMAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/30/2017 1:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 4025' and pumped 800 # gel followed by 60 sx cement w/200 # hulls. Pulled tubing to 2750' and pumped 135 sx cement w/100 # hulls. Pulled tubing to 1375' and pumped 130 sx cement w/50 # hulls to circulate cement to surface. Pulled all tubing. Topped off 5 1/2' casing with 15 sx cement. Hooked to 8 5/8" x 5 1/2" annulus and pressure immediately to 300 psi.

GPS: 39.95661N -100.84016W

Perfs:

Top	Bot	Thru	Comments
4071	4075		

Remarks: GLOBAL OILFIELD SERVICES TICKET # 3125

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

KCC WICHITA

(TECHNICIAN)

CM

SEP 28 2017

RECEIVED

SEP 07 2017

Form CP-2/3

INVOICED
OCT 11 2017