

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-165-21991-00-00  
Spot: SENWSWNW Sec/Twnshp/Rge: 31-18S-17W  
3479 feet from S Section Line, 4888 feet from E Section Line  
Lease Name: WARD Well #: 1-31  
County: RUSH Total Vertical Depth: 3851 feet

Operator License No.: 30717  
Op Name: DOWNING-NELSON OIL CO INC  
Address: PO BOX 1019  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3710		WITH 2 SX CMT
PROD	5.5	3851	2420	WITH 125 SX CMT
SURF	8.625	1130		WITH 450 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/15/2017 10:30 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: CIBP @ 3710' WITH 2 SX CMT. PLUG AT 1180' WITH 12 SX GEL & 50 SX CMT. PLUG AT 640' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KEN SCOFIELD Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/15/2017 1:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 3710' WITH 2 SX CMT. 1ST PLUG AT 1150' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 635' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 35 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
3763	3765		
3758	3762		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed [Signature]

(TECHNICIAN)

RECEIVED  
SEP 18 2017  
KCC DODGE CITY

SA

INVOICED  
OCT 11 2017