

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-04993-00-00
Spot: SWNE Sec/Twnshp/Rge: 32-20S-12W
990 feet from N Section Line, 990 feet from E Section Line
Lease Name: MCCULLOUGH BRYANT A Well #: 3
County: BARTON Total Vertical Depth: 3479 feet

Operator License No.: 5042
Op Name: EDMISTON OIL COMPANY, INC.
Address: 125 N MARKET STE 1420
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3465		100 SX
SURF	8.625	276		275 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/31/2017 12:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: SHANNON RAYBERN Company: EDMISTON OIL COMPANY, INC. D Phone: (620) 793-2672

Proposed Plugging Method: Ordered 225 sx 60/40 pozmix 4% gel cement w/600 # hulls, 225 sx common cement with 3% cc.

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE
Date/Time Plugging Completed: 08/31/2017 12:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Old abandoned well with 4 1/2" casing. Junk in hole at 1352'. Will plug from there.
Perforated at 1300', 670' and 250'. Ran tubing to 1250' and pumped 40 sx cement w/3% cc.
Had returns. Pulled tubing to 650' and pumped 150 sx cement w/3% cc and 200 # hulls. No
returns. Shut down for 2 hours. Tagged at 670'. Ran tubing to 650' and pumped 130 sx
cement. Cement did not circulate. Shut down for the day.
09/01/2017- Tagged cement at 100' and pumped 15 sx cement. Cement circulated on casing.
GPS: 38.27271 -098.66737

Perfs:

Top	Bot	Thru	Comments
3389	3395		
3369	3373		

Remarks: QUALITY OILWELL CEMENTING

Plugged through: TBG

District: 04

Signed Bruce Rodie

(TECHNICIAN)

CJM

KCC WICHITA

SEP 28 2017

RECEIVED

SEP 07 2017

SEP 07 2017

Form CP-2/3

INVOICED
09 11 2017