

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-193-21000-00-00
Spot: SWNWNE Sec/Twnshp/Rge: 24-9S-32W
335 feet from N Section Line, 1095 feet from E Section Line
Lease Name: B & M ALBERS Well #: 1
County: THOMAS Total Vertical Depth: 4678 feet

Operator License No.: 34117
Op Name: ETERNITY EXPLORATION, LLC
Address: 338 SPYGLASS DR
COPPELL, TX 75019

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	248		175 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/30/2017 12:00 AM
Plug Co. License No.: 34743 Plug Co. Name: WHITE KNIGHT DRILLING LLC
Proposal Rcvd. from: TERRY Company: WHITE KNIGHT DRILLING LLC Phone: (785) 303-8005

Proposed Plugging Method: Ordered 240 sx 60/40 pozmix - 4% gel cement with 1/4# flo-seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER WitnessType: NONE
Date/Time Plugging Completed: 08/30/2017 2:30 PM KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

Perfs:

1st plug @2630 w/50 sx
2nd plug @1775 w/100 sx
3rd plug @300 w/50 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Remarks: SOS

Plugged through: DP

INVOICED
OCT 11 2017

District: 04

Signed Ed Schumacher
(TECHNICIAN)

CM

KCC WICHITA

SEP 28 2017

RECEIVED

SEP 12 2017