

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-185-23087-00-02  
Spot: N2NESENE Sec/Twnshp/Rge: 10-21S-11W  
3751 feet from S Section Line, 320 feet from E Section Line  
Lease Name: FAIR B OWWO Well #: 1-10  
County: STAFFORD Total Vertical Depth: 3475 feet

Operator License No.: 5056  
Op Name: F. G. HOLL COMPANY L.L.C.  
Address: 9431 E CENTRAL STE 100  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2280		WITH 2 SX CMT
CIBP		3046		WITH 2 SX CMT
CIBP		3190		
PROD	5.5	3473	0	WITH 250 SX CMT
SURF	8.625	222		WITH 225 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/22/2017 9:30 AM  
Plug Co. License No.: 8253 Plug Co. Name: G & L WELL SERVICE, INC.  
Proposal Rcvd. from: ROB LONG Company: FG HOLL COMPANY Phone: (620) 793-0915

Proposed Plugging Method: CIBP @ 3046' WITH 2 SX CMT. CIBP @ 2280' WITH 2 SX CMT. PERFORATE AT 510' THEN PUMP 12 SX GEL AHEAD OF 120 SX CMT. CIRCULATE TO SURFACE. IF NO CIRCULATION PUMP FROM TOP TO FILL ANNULUS.

Plugging Proposal Received By: HEITH WALSH Witness Type: PARTIAL  
Date/Time Plugging Completed: 09/22/2017 11:00 AM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SET CIBP @ 3046' WITH 2 SX CMT. SET CIBP @ 2280' WITH 2 SX CMT. PERFORATE AT 510'. PUMPED 12 SX GEL & CIRCULATED CMT TO SURFACE WITH 135 SX CMT IN & OUT 5 1/2" X 8 5/8" ANNULUS.

Perfs:

Top	Bot	Thru	Comments
3096	3130		LKC
2333	2348		TARKIO

INVOICED  
OCT 11 2017

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

RECEIVED  
SEP 26 2017  
KCC DODGE CITY

Signed: [Signature] ECRS  
(TECHNICIAN)

SA