

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-25497-00-00
Spot: S2S2S2 Sec/Twnshp/Rge: 32-12S-17W
330 feet from S Section Line, 2640 feet from W Section Line
Lease Name: NUSS-SCHMEIDLER UNIT Well #: 1
County: ELLIS Total Vertical Depth: 3665 feet

Operator License No.: 5135 String Size Depth (ft) Pulled (ft) Comments
Op Name: FARMER, JOHN O., INC. PROD 5.5 3663 150 SX
Address: 370 W WICHITA AVE PO BOX 352 SURF 8.625 208 160 SX
RUSSELL, KS 67665

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/21/2017 9:00 AM
Plug Co. License No.: 5135 Plug Co. Name: FARMER, JOHN O., INC.
Proposal Rcvd. from: VAL DREHER Company: FARMER, JOHN O., INC. Phone: (785) 483-8356

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement, 10 sx gel (100 #) and 500 # hulls.
Alt II from 1290' to surface w/150 sx cement.
Production perforations: 3612' - 3624'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/21/2017 12:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3400' and pumped 10 sx gel followed by 50 sx cement w/300# hulls. Pulled tubing to 1850' and pumped 185 sx cement w/200 # hulls to circulate cement to surface. Pulled all tubing. Topped off 5 1/2" casing with 15 sx cement. Hooked to 8 5/8" x 5 1/2" annulus and pressured to 200 psi immediately.

GPS: 38.95908 -09923353

Perfs:

Top	Bot	Thru	Comments
3612	3624		ARBUCKLE

Remarks: QUALITY OILWELL CEMENTING TICKET # 396

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

KCC WICHITA

SEP 28 2017

RECEIVED

SEP 21 2017

INVOICED
OCT 11 2017