

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-19044-00-01  
Spot: N2SENVSE Sec/Twnshp/Rge: 33-20S-14W  
1665 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: HAHN Well #: 3  
County: BARTON Total Vertical Depth: 2483 feet

Operator License No.: 5056

String Size Depth (ft) Pulled (ft) Comments

Op Name: F. G. HOLL COMPANY L.L.C.

PROD 5.5 2470 225 SX

Address: 9431 E CENTRAL STE 100  
WICHITA, KS 67206

SURF 8.625 830 200 SX

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 09/19/2017 8:00 AM

Plug Co. License No.: 34069

Plug Co. Name: BASIC ENERGY SERVICES, LP

Proposal Rcvd. from: ROB LONG

Company: F. G. HOLL COMPANY L.L.C. DBA Phone: (620) 793-0915

Proposed  
Plugging  
Method:

Ordered 350 sx 60/40 pozmix 4% gel cement w/300 # hulls.

Plugging Proposal Received By: BRUCE RODIE

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 09/19/2017 2:00 PM

KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Perforated at 1350' and 830'. Ran tubing to 2308' and pumped 100 sx cement w/200 # hulls.  
Pulled tubing to 1350' and pumped 65 sx cement. Pulled tubing to 811'. Circulated cement to  
surface with 200 sx cement on casing and surface pipe. Topped off with 10 sx cement.

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 2326 | 2332 |      |          |

GPS: 38.26575 -098.87238

Remarks: BASIC ENERGY SERVICES

Plugged through: TBG

District: 04

Signed

*Bruce Rodie*

(TECHNICIAN)

CM

KCC WICHITA

SEP 28 2017

RECEIVED

SEP 22 2017

Form CP-2/3

INVOICED  
OCT 11 2017