

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-137-20479-00-00  
Spot: NENWSWNE Sec/Twnshp/Rge: 34-2S-24W  
1400 feet from N Section Line, 2110 feet from E Section Line  
Lease Name: ELLA MAE Well #: 34-2  
County: NORTON Total Vertical Depth: 3772 feet

Operator License No.: 33335  
Op Name: IA OPERATING, INC.  
Address: 785 W. COVELL ROAD, SUITE 200  
EDMOND, OK 73003

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3771		125 SX
SURF	8.625	262		175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/11/2017 12:00 PM  
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE  
Proposal Rcvd. from: TOM BERENS Company: IA OPERATING, INC. Phone: (785) 639-5727

Proposed Plugging Method: Ordered 325 sx 60/40 pozmix 4% gel cement, 500 # hulls and 10 sx gel.  
Alt II: 2031' to surface with 235 sx cement.  
Production perforations: 3508' - 3511'

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/11/2017 5:15 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3500' and pumped 10 sx gel followed by 50 sx cement w/250 # hulls. Pulled tubing to 2031' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1000' and pumped 100 sx cement w/50 # hulls to circulate cement to surface. Pulled all tubing. Topped off 5 1/2" casing with 20 sx cement. Hooked to 8 5/8" x 5 1/2" annulus with immediate pressure to 300 psi.

GPS: 39.83835N -100.00912W

Perfs:

Top	Bot	Thru	Comments
3508	3511		

INVOICED  
OCT 11 2017

Remarks: QUALITY OILWELL CEMENTING TICKET # 382

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

*Pat Bedore*

(TECHNICIAN)

cm

KCC WICHITA

SEP 28 2017

RECEIVED

SEP 21 2017