

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-137-20472-00-00

Spot: SENWNWNE

Sec/Twnshp/Rge: 34-2S-24W

500 feet from N Section Line, 2220 feet from E Section Line

Lease Name: ELLA MAE

Well #: 34-1

County: NORTON

Total Vertical Depth: 3768 feet

Operator License No.: 33335

String Size Depth (ft) Pulled (ft) Comments

Op Name: IA OPERATING, INC.

PROD 5.5 3767 125 SX

Address: 785 W. COVELL ROAD, SUITE 200
EDMOND, OK 73003

SURF 8.625 244 170 SX

T1 2.875 3547

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/12/2017 10:00 AM

Plug Co. License No.: 32128

Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE

Proposal Rcvd. from: TOM BERENS

Company: IA OPERATING, INC.

Phone: (785) 639-5727

Proposed Plugging Method: Ordered 325 sx 60/40 pozmix 4% gel cement w/500 # hulls and 10 sx gel.
Alt II: 2035' w/300 sx cement.
Production perforations: 3513' - 3516'.

Plugging Proposal Received By: RICHARD WILLIAMS

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 09/12/2017 1:00 PM

KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3500' and pumped 10 sx gel followed by 50 sx cement w/250 # hulls. Pulled tubing to 2031' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1000' and pumped 100 sx cement w/50 # hulls to circulate cement to surface. Pulled all tubing. Topped off 5 1/2" casing with 15 sx cement. Hooked to 8 5/8" x 5 1/2" annulus and immediately pressured to 300 psi.

GPS: 39.83835N -100.00912W

Perfs:

Top	Bot	Thru	Comments
3513	3516		

Remarks: QUALITY OILWELL CEMENTING TICKET # 383

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

KCC WICHITA

SEP 28 2017

RECEIVED

SEP 21 2017

Form CP-2/3

INVOICED
OCT 11 2017