

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-20521-00-01

Spot: SESENW Sec/Twnshp/Rge: 17-18S-29W

2310 feet from N Section Line, 2310 feet from W Section Line

Lease Name: SCHWARTZ

Well #: 1-17 OWWO

County: LANE

Total Vertical Depth: 4625 feet

Operator License No.: 3842

String	Size	Depth (ft)	Pulled (ft)	Comments
PC	5.5	2146		WITH 210 SX CMT
PROD	5.5	4624	0	WITH 225 SX CMT
SURF	8.625	206		WITH 140 SX CMT

Op Name: LARSON ENGINEERING, INC. DBA LAR

Address: 562 W STATE RD 4
OLMITZ, KS 67564

Well Type: Oil

UIC Docket No:

Date/Time to Plug: 09/15/2017 10:00 AM

Plug Co. License No.: 32382

Plug Co. Name: SWIFT SERVICES, INC.

Proposal Recd. from: TOM LARSON

Company: LARSON OPERATING

Phone: (620) 653-7368

Proposed: RUN TBG TO 4556' & PUMP 20 SX GEL, 50 SX CMT & 200# HULLS. PULL TBG TO 2170' & PUMP 10 SX GEL & 30 SX CMT. PULL TBG TO 1300' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF, TIE ONTO BACKSIDE & PUMP CMT UNTIL 300# PRESSURE.

Plugging Proposal Received By: STEVE PFEIFER

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 09/15/2017 2:00 PM

KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4550' & PUMPED 20 SX GEL, 50 SX CMT & 200# HULLS. PULLED TBG TO 2170' & PUMPED 10 SX GEL & 30 SX CMT. PULLED TBG TO 1300' & PUMPED 130 SX CMT. CMT CIRCULATED TO PIT. PULLED TBG & TOPPED OFF WITH 10 SX CMT. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
4550	4556		
4388	4390		
4274	4282		

INVOICED

OCT 11 2017

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.


Plugged through: TBG

District: 01

Signed



(TECHNICIAN)



RECEIVED

SEP 19 2017

KCC DODGE CITY