

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-207-23939-00-00
Spot: SWNWSESE Sec/Twnshp/Rge: 28-25S-15E
987 feet from S Section Line, 1137 feet from E Section Line
Lease Name: HARTZLER Well #: 40
County: WOODSON Total Vertical Depth: 1200 feet

Operator License No.: 33900

Op Name: LEIS, STEVEN A.

Address: 1135 30TH RD
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	1200		120 SX
SURF	7	40		10 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 07/31/2017 12:00 AM

Plug Co. License No.: 33900

Plug Co. Name: LEIS, STEVEN A.

Proposal Rcvd. from: STEVE LEIS

Company:

Phone: (620) 330-6328

Proposed
Plugging
Method:

Stage Plugs 50ft plug at TD 50ft plug at the BKC Plug from 250ft to Surface

Plugging Proposal Received By:

Witness Type: PARTIAL

Date/Time Plugging Completed: 07/31/2017 12:00 PM

KCC Agent: RYAN DULING

Actual Plugging Report:

Perfs:

Ran 1" pipe down the inside of the 2.875" casing to TD. Pumped and placed 50' cement plug at TD. Pulled pipe to 775'. Pumped and placed 50' plug at 775'. Pulled pipe to 250'. Pumped and circulated cement from 250' to surface. A total of 12 sacks of portland cement was reported used to plug this well.

RECEIVED
KCC DIST # 3
SEP 27 2017
CHANUTE, KS

RD

INVOICED
EST 11 7 2017

Remarks: WELL PLUGGED DUE TO COMPLIANCE AGREEMENT.

Plugged through: TBG

District: 03

Signed

[Signature]
(TECHNICIAN)