

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-21919-00-00
Spot: SWNWSESW Sec/Twnshp/Rge: 11-30S-9W
800 feet from S Section Line, 1550 feet from W Section Line
Lease Name: ZENDA TOWNSITE "A" GU Well #: 1-11
County: KINGMAN Total Vertical Depth: 4297 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 9342 E CENTRAL
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4296		125 SX
SURF	8.625	223		275 SX
T1	2.375	4356		

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 08/01/2017 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: (316) 636-2737

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/28/2017 11:30 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 4230' & CAPPED WITH 2 SKS CEMENT. THE 4 1/2" CASING WAS RECOVERED FROM 2880' & PULLED TO 1450', WHERE 800# OF GEL & 50 SX OF CEMENT WAS PUMPED. THE CASING WAS PULLED TO 900', WHERE 35 SX OF CEMENT WAS SPOTTED. THE CASING WAS PULLED TO 280' WHERE CEMENT WAS CIRCUALTED TO SURFACE WITH 110 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
4280	4288		

INVOICED
OCT 11 2017

Remarks: QUALITY WELL SERVICE, COMMON CEMENT

Plugged through: CSG

District: 02

Signed [Signature] DISTRICT SUPERVISOR
(TECHNICIAN)