

15.159.00429.0000

6-4

2-070463

105
R

RECEIVED
KANSAS CORPORATION COMMISSION

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

JUL 1 1992

API NUMBER: 10/12/61

CONSERVATION DIVISION
WICHITA, KS

SE NW NE , SECTION 2 TOWNSHIP 21 RANGE 9W

OPERATOR LICENSE # 5131 4290 FEET FROM S SECTION LINE
1650 FEET FROM E SECTION LINE

OPERATOR Thunderbird Drilling
NAME & P. O. Box 97
ADDRESS Ellinwood, KS 67526

LEASE NAME: T.S.U. #9-1
COUNTY: Rice

WELL TOTAL DEPTH: 3395' PA 3368'

110.33

CONDUCTOR PIPE: _____

SURFACE CASING: 8-5/8" @ 207'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SLD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Kelso Casing
ADDRESS: Chase, KS 67524 LICENSE: 6050

COMPANY TO PLUG AT: HOUR: 9:00 DAY: 4 MONTH: 6 YR: 1992

PLUGGING PROPOSAL RECEIVED FROM: Vernon Dunce
COMPANY NAME: Kelso Casing PHONE: _____

WERE: Sand to 3270' & 5 sx - 35 sx @ 1200' - 35 sx @ 700' - 300' to surface.

PLUGGING PROPOSAL RECEIVED BY: Phil Worley

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART (_____) NONE (_____)

COMPLETED: HOUR: 12:30 DAY: 4 MONTH: 6 YEAR: 1992

ACTUAL PLUGGING REPORT:
Sanded bottom to 3270' & 5 sx common - well had been squeezed thru the salt section, so could not get below 800' - pulled to 700' & pumped 40 sx - pulled to 300' & circ to surf.

REMARKS: Allied #1801 60/40 4%

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE 7-8-92

INV. NO. 35640

JS

Jack Luthi (AGENT)

FORM CP-2/3
REV. 3/90

De



WELEX

RADIATION GUARD LOG

COMPANY Thunderbird Drilling, Inc.

WELL Faler #1 (T.S.U. 9-1)

FIELD Wildcat

COUNTY Rice STATE Kansas

Location SE NW NE

Other Services:

Sec. 2 Twp 215 Rge 9W

Permanent Datum Ground level Elev. _____

Log Measured From K.B. 4 Ft. Above Perm. Datum

Drilling Measured From Kelly Bushing

Elev.: K.B. 1681

D.F. _____

G.I. 1676

Date	10-12-61	10-12-61	10-12-61	
Run No.	ONE	GAMMA	NEUTRON	GUARD
Depth-Driller			3395	3395
Depth-Welex			3383	3383
Btm. Log Inter.			3383	3378
Top Log Inter.			2650	2650
Casing-Driller	@	@	95/B @ 207	W/190.5A
Casing-Welex				
Bit Size			7 7/8	
Type Fluid in Hole			Salt Gel	
Dens.			9.5	44
Visc.				
pH			6.5	11
Fluid Loss		ml		ml
Source of Sample			Circ. Pit	
R _m @ Meas. Temp.	@ °F	@ °F	.086 @ 80 °F	@ °F
R _{mf} @ Meas. Temp.	@ °F	@ °F	.166 @ 80 °F	@ °F
R _{mc} @ Meas. Temp.	@ °F	@ °F	.145 @ 80 °F	@ °F
Source R _{mf} R _{mc}			Meas Meas.	
R _m @ BHT	@ °F	@ °F	.06 @ 104 °F	@ °F
Time Since Circ.			4 Hrs	
Max. Rec. Temp.	@ °F	@ °F	@ 104 °F	@ °F
Equip. Location	4946 GT. RD.			
Recorded By	Horlison & Kreutz			RECEIVED
Witnessed By	Mc. Diakins			STATE CORPORATION COMMISSION

MAY 1 1992

CONSERVATION DIVISION
Wichita Kansas