

2-070635

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

8-9

API NUMBER: 15-159.06622.0000

NW NW SE, SECTION 2 TOWNSHIP 21 RANGE 9W

OPERATOR LICENSE # 3911 2310 FEET FROM S SECTION LINE
OPERATOR RAMA OPERATING COMPANY INC 2310 FEET FROM E SECTION LINE
NAME & BOX 159
ADDRESS STAFFORD, KS 67578

LEASE NAME: SCHAFER #2
COUNTY: RICE
WELL TOTAL DEPTH: 3352' 108.94
PIPE: 5 1/2" @ 3352'
SURFACE CASING: 8 5/8" @ 224'

ABANDONED OIL WELL ☒ GAS WELL ☐ INPUT WELL ☐ SWD ☐ D&A ☐

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: MIKE'S TESTING & SALVAGE INC
ADDRESS: P.O. BOX 159. CHASE, KS 67524 LICENSE: 31529

COMPANY TO PLUG AT: HOUR: 12:00 DAY: 9 MONTH: 8 YR: 1996

PLUGGING PROPOSAL RECEIVED FROM: MANNY
COMPANY NAME: MIKE'S TESTING & SALVAGE INC PHONE: _____
WERE: SAND TO 2900' AND 5 SACKS
35 SACKS AT 1230'
35 SACKS AT 750'
275' TO SURFACE

PLUGGING PROPOSAL RECEIVED BY: J.L.

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE (☒)

COMPLETED: HOUR: 4:30 DAY: 9 MONTH: 8 YEAR: 1996

ACTUAL PLUGGING REPORT: SANDED BOTTOM TO 2900' AND 5 SACKS OF COMMON. SHOT 5 1/2" CASING OFF AT 1316'. PULLED TO 1230'. PUMPED 35 SACKS. PULLED TO 750'. PUMPED 35 SACKS. PULLED TO 275'. CIRCULATED CEMENT TO SURFACE.

RECEIVED

KANSAS CORPORATION COMMISSION

SEP 05 1996

REMARKS: 60/40 POZ 4% GEL ALLIED #4250

CONSERVATION DIVISION
WICHITA KS

INVOICED

SEP 05 1996

DATE

INV. NO.

46433

I DID NOT OBSERVE THIS PLUGGING.

JACK LUTHI

FORM CP-2/3
REV. 7/96