

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-30073-00-00 Spot: SW NE SE
Sec: 2 Twnshp & Dir: 21 S Rng & Dir: 2 W
Feet: 1650 frm N/S: S Feet: 990 frm E/W: E
Lease/Unit Name: SCHAFFER Well Number: 4
County: RICE Total Vertical Depth: 2955 feet

Operator License No.: 3911
Operator Name: Rama Operating Co., Inc.
Address: 101 S. Main
Stafford, KS 67578

5/3

Conductor Pipe: Size feet:
Surface Casing: Size 8.62 feet: 225
Production: Size 5.5 feet: 2948 96.04

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/03/2000 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: Mike's Testing & Salvage, Inc.
Proposal Received from: Monteg Joe Company Name: Mike's Testing & Salvage, Inc.
OpRepPhoneNo: (316) 938-2943

Were: Sand to 2680 and 5sxs. 35sxs-1150. 35sxs-750. 275-0

Plugging Proposal Received By: Jack Luthi WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/03/2000 5:00 PM

Actual Plugging Report:

Sanded bottom to 2680 and 5sxs of common shot 5 1/2" casing off at 1575. Pulled to 1150 and pumped 35sxs. Pulled to 750' pumped 35sxs pulled to 275' and cir. Cement to surface.

RECEIVED
KCC DISTRICT #2

MAY 09 2000

Remarks: Allied # 3986 60/40 poz 4%gel
Anhydrite Plug: No BottomPlug: DakotaPlug: No
Plugged through:

I (did / did not) observe this plugging.

Signed

Jack Luthi
(TECHNICIAN)

INVOICED

DATE

5/17/00

INV. NO.

61733