

To: 1 010046  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,237.0000

SW SW NW, SEC. 4, T 21 S, R 12 W/E

2970 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

Lease Name Wise Well # 1

Operator: Hummon Corporation  
Name & Address: 400 One Main Place  
Wichita, KS 67202

County Stafford 115.05

Well Total Depth 3540 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 292 ✓

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:45 am Day: 14 Month: November Year: 19 85

Plugging proposal received from Vernon Duntz

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 3536' PBD 3502' Perfs at 3334-3338'; 3350-3352'; 3365-3371'

1st plug sand back to 3280' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:20 am Day: 14 Month: November Year: 1985

ACTUAL PLUGGING REPORT 1st plug sanded back to 3280' and dumped 5 sx cement on top of sand

through bailer, 2nd plug squeezed well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 150 sx cement.

Maximum pressure 400 psi and shut in 50 psi.

Remarks: Recovered 2700' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE NOV 26 1985

INV. NO. 11222

RECEIVED STATE CORPORATION COMMISSION

NOV 20 1985

Signed Jack P. Luthi (TECHNICIAN)