

1030286

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-22,071.0000

TECHNICIAN'S PLUGGING REPORT

NW SW NE, SEC. 4, T 21 S, R 12 W/X
3630 feet from N SE Corner of
2310 feet from W SE Corner of
section line
section line

Operator License # 9800

Lease Name Spacil Well # 4-1R

Operator: Double R. Oil Company

County Stafford

Name & Address P. O. Box 506

Well Total Depth 3540 115.05 feet

McCook, NE 69001

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 268

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Emphasis Oil Operations License Number 8241

Address P. O. Box 506, Russell, KS 67665-0506

Company to plug at: Hour: 11:00 am Day: 24 Month: September Year: 19 84

Plugging proposal received from Greg Flax

(company name) Emphasis (phone) 913-483-3518

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 3430' with 40 sx cement

2nd plug at 630' with 50 sx cement

3rd plug at 390' with 60 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement, 7th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Steve Stewart
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:00 pm Day: 24 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 3430' with 40 sx cement, 2nd plug at 630' with 50 sx cement, 3rd plug at 300' with 60 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 10 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 09 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

Cons. Div. DIVISION
Wichita, Kansas

INVOICED

observe this plugging.

Signed Steve Stewart
(TECHNICIAN)

DATE 10-11-84

INV. NO. 4226