

1 080166

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-21,956.0000

SW NW SW, SEC. 4, T. 21 S, R. 12 ~~W/E~~

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7383

Lease Name Setser Well # 1

Operator: Grady Bolding, Corporation

County Stafford

Name & Address Box 244

Well Total Depth 3485 8113.26 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 244, Great Bend, KS 67530

Company to plug at: Hour: 6:00 am Day: 18 Month: June Year: 19 84

Plugging proposal received from D. B. (Deacon) Pulley

(company name) Rockhold (phone) 316-792-2506

were: 5 1/2 set at 3479 Top perf 3252-34'

1st plug sand back to 3200' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump an additional 100 sx cement

RECEIVED

STATE CORPORATION COMMISSION

Plugging Proposal Received by J. A. [Signature]

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 am Day: 18 Month: June Year: 19 84

CONSERVATION DIVISION
Wichita, Kansas

ACTUAL PLUGGING REPORT 5 1/2 set at 3479' Top perf 3252-34'

1st plug sanded back to 3200' and dumped 5 sx cement on top of sand through bailer,

2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

and released 8 5/8" rubber plug and pumped an additional 100 sx cement.

Maximum pressure 500# and shut in pressure 200#

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun. They recovered 2600' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

INVOICED

Signed J. A. [Signature]

(TECHNICIAN)

DATE 6-29-84

INV. NO. 2210