

1 010246

MAY 24 1987

API NUMBER 15-185-22,436-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION C W/2  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE SW, SEC. 4, T 21 S, R 12 W/E

1980 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5923

Lease Name Hewitt Well # 1

Operator: American Petroleum Company, Inc.

County Stafford 113.26

Name & Address 3500 North Rock Road, Suite 1300  
Wichita, KS 67226

Well Total Depth 3485 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 271

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Emphasis Oil Operations License Number 8241

Address Box 819, Russell, KS 67665

Company to plug at: Hour: 12:30 p.m. Day: 24 Month: 5 Year: 19 87

Plugging proposal received from Bill Owens

(company name) Emphasis Oil Operations (phone) 913-483-3518

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1844'  
Anhydrite 636-665'

1st plug at 3430' with 20 sx cement, 2nd plug at 665' with 50 sx cement,

3rd plug at 300' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Jack Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:45 p.m. Day: 24 Month: 5 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 3430' with 20 sx cement,

2nd plug at 665' with 50 sx cement,

3rd plug at 300' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied.

JUN 2 1987

(If additional description is necessary, use BACK of this form)  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED  
Observe this plugging.

DATE 6-3-87

Signed *Jack Luthi*  
(TECHNICIAN)

INV. NO. 17136

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date MAY 15 1987 month day year

API Number 15-185-22,436 0000

OPERATOR: License # 5923 AMERICAN PETROLEUM COMPANY, INC. 3500 NORTH ROCK ROAD, #1300 WICHITA, KANSAS 67226 JAMES T. BARVAIS (316) 684-5273

C.W/2.NE.SW. Sec. 4 Twp. 21. S, Rg. 12. X West 1980 Fl. from South Line of Section 3630 Fl. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 8241 EMPHASIS OIL OPERATIONS Box 819 RUSSELL, KANSAS 67665

Nearest lease or unit boundary line 330 feet County STAFFORD Lease Name HEWITT Well # 1 Ground surface elevation 1844 feet MSL Domestic well within 550 feet yes X no Municipal well within one mile yes X no Depth to bottom of fresh water 80 Depth to bottom of usable water 250 Surface pipe by Alternate 1XX 2 Surface pipe planned to be set 250 Conductor pipe required NONE Projected Total Depth 3500 feet Formation ARBUCKLE

Well Drilled For: X Oil SWD X Infield X Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date 5-6-87 Signature of Operator or Agent Title PRESIDENT

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 250 feet per 100 This Authorization Expires 11-6-87 Approved By 5-6-87

PER JACK LUTHI 5-4-87

C.W/2.NE.SW. Sec. 4 Twp. 21. S, Rg. 12. X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 3500 (ARBUCKLE) feet depth with 25 SXS of 60/40 POZMIX, 6% GEL. 2nd plug @ 1200 (ANHYDRITE) feet depth with 50 SXS of 60/40 POZMIX, 6% GEL. 3rd plug @ 250 (BASE SURFACE) feet depth with 50 SXS of 60/40 POZMIX, 6% GEL. 4th plug @ 0 TO 10 feet depth with 40 SXS of 60/40 POZMIX, 6% GEL. 5th plug @ feet depth with SXS of (2) Rathole with 15 SXS (b) Mousehole with 10 SXS \* IF APPLICABLE

Table with columns: PUSHER, TD, SURFACE PIPE, ANHYDRITE, STARTING TIME & DATE, COMPLETION TIME & DATE, 1st PLUG @ FT. W/ SX, 2nd PLUG @ FT. W/ SX, 3rd PLUG @ FT. W/ SX, 4th PLUG @ FT. W/ SX, RAT HOLE CIRCULATED W/ SX, MOUSE HOLE CIRCULATED W/ SX, WATER WELL PLUGGED W/ SX, CEMENT COMPANY, TECHNICIAN

RECEIVED STATE CORPORATION COMMISSION

JUN 2 1987

CONSERVATION DIVISION Wichita, Kansas

10:45 xlog