

15-185-13031-00-02

Parrish will cancell the Docket No. E-09,481 Comp. 9-24-52

1 010071  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- NW NE NE , SEC. 4 , T 21 S, R 12 W/EX

4950 feet from S section line

790 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5228

Lease Name Spacil Well # 7

Operator: Parrish Corporation

County Stafford 111.87

Name & Address 100 S. Market, Suite 200

Well Total Depth 3442 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 280

Abandoned Oil Well Gas Well Input Well SWD Well x D&A

Other well as hereinafter indicated

Plugging Contractor Parrish Corporation License Number 5228

Address 100 S. Market, Suite 200, Wichita, KS 67202

Company to plug at: Hour: 3:40 pm Day: 14 Month: January Year: 19 86

Plugging proposal received from Lavern Brown

(company name) Parrish (phone) 316-263-8726

were: 5 1/2" at 3417' Anhydrite at 600' 5 1/2" casing cemented from 3418' to 2700'

1st plug squeeze well with 2 sx hulls, 30 sx cement, 15 sx gel, and 100 sx cement

2nd plug pump 100 sx cement down the Annulus

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 4:30 pm Day: 14 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug squeezed well with 2 sx hulls, 30 sx cement, 15 sx gel, and 100 sx cement. Pumped 100 sx cement down 8 5/8" x 5 1/2" Annulus

Maximum pressure on the squeeze 600 psi and shut in 200 psi

Maximum pressure on the Annulus 500 psi and shut in 500 psi

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No recovery. (If additional description is necessary, use BACK of this form.)

INVOICED

DATE FEB 5 1986

INV. NO. 12319

Signed [Signature] (TECHNICIAN)

JAN 27 1986

CONSERVATION DIVISION 1-27-86