

To: 1 120505
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,440.0000 ³²⁹
E/2 SE SW, SEC. 15, T 21 S, R 13 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 6412
Operator: Sid Tomlinson
Name & Address 1802 Wildwood Dr.
Stillwater Okla. 74075

660 feet from S section line
2970 feet from E section line
Lease Name Herb Well # 2
County Stafford 120.77
Well Total Depth 3716 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 332

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address Box 176 Chase Ks 67524

Company to plug at: Hour: 8⁰⁰ AM Day: 13 Month: 12 Year: 19 90

Plugging proposal received from Millard Kelso
(company name) Kelso Casing Pulling (phone) 316-938-2943

were: Sand 5 1/2" casing back to 3280' & 55x cement @ dump bailer
Pump in 8 5/8" surface casing @ 300# hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100# hulls, 8 5/8" wiper plug & 150 sx cement
Recovered: 2440' of 5 1/2" casing
5 1/2" casing set @ 3715' cemented @ 150 sx cement PBD @ 3550' Ref @
3331-3470' Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9³⁰ AM Day: 13 Month: 12 Year: 19 90

ACTUAL PLUGGING REPORT Sanded 5 1/2" casing back to 3280' & 55x cement @ bailer
Pumped into 8 5/8" surface casing @ 300# hulls, 10 sx gel, 50 sx
Cement, 10 sx gel, 8 5/8" wiper plug, 100# hulls & 150 sx cement.

Pumping pressure 0-300# Shut in pressure 50#

Remarks: Cemented by Allied - 60-40 prr @ 67 gel
(If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

DEC 16 1990
Signed Duane Rankin
(TECHNICIAN)

DATE 1-16-91
INV. NO. 30507