

To: 1 051988  
STATE CORPORATION COMMISSION 12-12  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-185-21,508-0001  
NE NW SW, SEC. 15, T 21 S, R 13 W/E  
2327 feet from S section line  
960 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30931  
Operator: Daystar Petroleum, Inc.  
Name & Address 1321 W. 93rd N.  
Valley Center, KS 67147-9136

Lease Name Herb A Well # 1  
County Stafford 119.86  
Well Total Depth 3688 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 288

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SMD Well \_\_\_\_\_ O&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529  
Address: P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 12 Month: 12 Year: 19 95

Plugging proposal received from Manny Boatwright  
(company name) Mike's Testing & Salvage Inc. (phone) 316-938-2943

logs: 5 1/2" at 3688' w/135 sx cement, PBT 3661', Perfs at 3642-44, 3652-56, 3474-80, 3494-3500, 3438-42, 3542-44', CIBP @ 3648'

1st plug sand back to 3375' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part X None \_\_\_\_\_  
Operations Completed: Hour: 10:20 a.m. Day: 12 Month: 12 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 3375' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down the 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 600 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1700' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 14 1995  
CONSERVATION DIVISION  
Wichita, Kansas

**INVOLVED**

DATE 1-5-96  
INV. NO. 44416

Signed Richard W. Lacey  
(TECHNICIAN)