

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-147-00724-00-00
Spot: NWSESESW Sec/Twnshp/Rge: 16-1S-18W
361 feet from S Section Line, 3095 feet from E Section Line
Lease Name: STAHN Well #: 1
County: PHILLIPS Total Vertical Depth: 3535 feet

Operator License No.: 31070
Op Name: EAGLE RIVER ENERGY CORPORATIO
Address: 7060 S YALE # 702
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3533		150 SX
SURF	8.625	191		125 SX

Well Type: EOR UIC Docket No: E06746.15 Date/Time to Plug: 08/29/2017 9:00 AM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Rcvd. from: JOHN MICKLE Company: EAGLE RIVER ENERGY CORPORA Phone: (620) 282-9034

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/700 # hulls.
Zone of inj. 3431' - 3480'.

Plugging Proposal Received By: PAT BEDORE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/29/2017 12:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3030' and pumped 100 sx cement w/300 # hulls. Pulled tubing to 2500' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1500' and pumped 140 sx cement w/100 # hulls to circulate cement to surface. Pulled all tubing. Topped off 5 1/2" casing with 15 sx cement. Shut in pressure 200 psi. Hooked to 8 5/8' x 5 1/2" annulus and pumped 50 sx cement. Shut in pressure 300 psi.

GPS: 39.95931N -099.35790W

Perfs:

Top	Bot	Thru	Comments
3470	3475		
3450	3454		
3431	3480		

Remarks: GLOBAL OILFIELD SERVICES TICKET # 3078

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

KCC WICHITA

SEP 28 2017

RECEIVED

SEP 07 2017