

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-179-00152-00-01
Spot: SWNWNWNW Sec/Twnshp/Rge: 6-9S-28W
4901 feet from S Section Line, 5044 feet from E Section Line
Lease Name: HOXIE WF (DECKER) Well #: 1
County: SHERIDAN Total Vertical Depth: 4410 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3885		125 SX
SURF	8.625	182		150 SX

Well Type: SWD UIC Docket No: D20457.0 Date/Time to Plug: 09/19/2017 8:30 AM
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE
Proposal Rcvd. from: DUANE EICHMAN Company: FARMER, JOHN O., INC. Phone: (785) 483-8355

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/400 # hulls.
8 5/8' surface casing set at 182' w/150 sx cement.
5 1/2' production casing set at 3885' w/125 sx cement.
TD 4410'. CIBP set at 2360'.
Casing perforated at 2350'. Cement circulated to surface with 450 sx cement.
Perforations: 2020' - 2070'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/19/2017 10:30 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 1970' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1050' and pumped 110 sx cement w/100 # hulls. Cement circulated to surface. Pulled tubing to surface. Connected to 5 1/2' production casing and pumped 15 sx cement. 8 5/8" surface casing observed to be full of cement.

GPS: 39.30590N -100.49662W

Perfs:

Top	Bot	Thru	Comments
2020	2070		

Remarks: QUALITY OILWELL CEMENTING TICKET # 393

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

cm

KCC WICHITA

SEP 28 2017

RECEIVED

SEP 21 2017
SEP 21 2017