

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-20793-00-01
Spot: NENW Sec/Twnshp/Rge: 6-11S-24W
4975 feet from S Section Line, 3576 feet from E Section Line
Lease Name: GARDNER Well #: 2
County: TREGO Total Vertical Depth: 4040 feet

Operator License No.: 33268
Op Name: RL INVESTMENT, LLC
Address: 2698 JO TERRACE
HILL CITY, KS 67642

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4040		150 SX
SURF	8.625	322		220 SX

Well Type: SWD UIC Docket No: D22014.0 Date/Time to Plug: 09/14/2017 9:30 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: LEON PFEIFER Company: RL INVESTMENT, LLC DBA Phone: (785) 627-6023

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/700 # hulls.
8 5/8" surface casing set at 322' w/220 sx cement.
4 1/2" production casing set at 4040' w/150 sx cement.
TD 4040'. PBTD 3955'.
Perforations: 3538' - 3862'.
Production casing was perforated at 1500' w/550 sx cement. Circulated cement to surface.
Anhydrite: 2046' - 2091'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/14/2017 1:50 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perfs:

Perforated production casing at 2068'. Ran tubing to 3500' and pumped 85 sx cement w/150 # hulls. Pulled tubing to 2600' and pumped 85 sx cement w/100 # hulls. Pulled tubing to 1300' and pumped 115 sx cement. Circulated cement to surface. Pulled tubing to surface. Connected to 4 1/2" production casing and pumped 20 sx cement. Connected to 8 5/8" surface casing and pumped 25 sx cement.

GPS: 39.13105N -100.03030W

INVOICED
OCT 12 2017

Remarks: SCHIPPERS OILFIELD SERVICES LLC TICKET # 607

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN) cm

KCC WICHITA
SEP 28 2017
RECEIVED

SEP 21 2017