

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-101-21956-00-00  
Spot: NESWSWNE Sec/Twnshp/Rge: 25-16S-27W  
2988 feet from S Section Line, 2263 feet from E Section Line  
Lease Name: KLITZE A Well #: 1-25  
County: LANE Total Vertical Depth: 4665 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		2216		WITH 615 SX CMT
PROD	4.5	4664	0	WITH 235 SX CMT
SURF	8.625	306		WITH 190 SX CMT

Well Type: EOR UIC Docket No: E28906.1 Date/Time to Plug: 09/22/2017 10:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Revd. from: MONTE BOYDSTON Company: TRANS PACIFIC OIL CORPORATIO Phone: (316)262-3596

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 40 SX CMT & 200# HULLS. SPACER TO 2230' THEN CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/22/2017 12:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4100' & PUMPED 40 SX CMT & 200# HULLS. PULL TBG TO 2247' & PUMPED 170 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 15 SX CMT. TIED ONTO BACKSIDE & PRESSURED TO 300#.

Perfs:

Top	Bot	Thru	Comments
4063	4068		


INVOICED  
OCT 12 2017

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED  
SEP 26 2017  
KCC DODGE CITY

5A