

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-21421-00-00
Spot: E2SWSESE Sec/Twnshp/Rge: 11-15S-29W
330 feet from S Section Line, 770 feet from E Section Line
Lease Name: MALANCO Well #: 3
County: GOVE Total Vertical Depth: 4030 feet

Operator License No.: 32457
Op Name: ABERCROMBIE ENERGY, LLC
Address: 10209 W. CENTRAL, STE 2
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4014		225 SX
SURF	8.625	266		180 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/18/2017 9:00 AM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: TIM JULIAN Company: ABERCROMBIE ENERGY, LLC DB Phone: (620) 793-8186

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement and 500 # hulls.
DV Tool at 883' w/285 sx cement.
Perforations: 3914' - 3921'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/18/2017 1:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Shot perforations at 1950'. Ran tubing to 3907' and pumped 75 sx cement w/250 # hulls.
Pulled tubing to 2901' and pumped 75 sx cement. Pulled tubing to 1995' and pumped 150 sx
cement. Cement circulated. Pulled tubing out. Topped off casing with 30 sx cement. Tied on
to backside and squeezed with 20 sx cement. Shut in pressure 200 psi.

GPS: 38.75880 -100.50622

Perfs:


Top	Bot	Thru	Comments
3914	3921		

Remarks: OES CEMENT TICKET # 53611

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

CM

KCC WICHITA
SEP 28 2017
RECEIVED

SEP 21 2017