

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-21418-00-00
Spot: N2NENE Sec/Twnshp/Rge: 14-15S-29W
4950 feet from S Section Line, 660 feet from E Section Line
Lease Name: MILLER B Well #: 5-14
County: GOVE Total Vertical Depth: 3980 feet

Operator License No.: 32457
Op Name: ABERCROMBIE ENERGY, LLC
Address: 10209 W. CENTRAL, STE 2
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3976		225 SX
SURF	8.625	279		180 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/14/2017 9:00 AM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: TIM JULIAN Company: ABERCROMBIE ENERGY, LLC DB Phone: (620) 793-8185

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.
DV Tool at 1216' w/500 sx cement.
Perforations: 3896' - 3902' and 3920' - 3925'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/14/2017 1:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Shot perforations at 1940'. Ran tubing to 3803' and pumped 75 sx cement w/250 # hulls.
Pulled tubing to 2899' and pumped 75 sx cement. Pulled tubing to 1992' and pumped 150 sx
cement. Cement circulated. Pulled tubing out. Topped off with 20 sx cement. Tied on to
backside and squeezed with 20 sx cement. Shut in pressure 200 psi.

GPS: 38.75689 -100.50592

Perfs:

Top	Bot	Thru	Comments
3920	3925		
3896	3902		

INVOICED


OCT - 3 2017

Remarks: QES CEMENT TICKET # 49562

Plugged through: TBG

District: 04

Signed _____



(TECHNICIAN)

CM

KCC WICHITA

SEP 28 2017

RECEIVED

SEP 21 2017