

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-21449-00-00
Spot: W2SENE Sec/Twnshp/Rge: 14-15S-29W
4290 feet from S Section Line, 495 feet from E Section Line
Lease Name: MILLER B Well #: 6-14
County: GOVE Total Vertical Depth: 3970 feet

Operator License No.: 32457
Op Name: ABERCROMBIE ENERGY, LLC
Address: 10209 W. CENTRAL, STE 2
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3970		180 SX
SURF	8.625	265		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/15/2017 9:00 AM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: TIM JULIAN Company: ABERCROMBIE ENERGY, LLC DB Phone: (620) 793-8185

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.
DV Tool at 1004' w/300 sx cement.
Perforations: 3892' - 3898' and 3913' - 3914'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/15/2017 1:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Shot perforations at 1940'. Ran tubing to 3791' and pumped 75 sx cement w/250 # hulls.
Pulled tubing to 2868' and pumped 75 sx cement. Pulled tubing to 1967' and pumped 125 sx
cement. Cement circulated. Pulled tubing out. Topped off casing with 45 sx cement. Tied on
to backside and squeezed with 20 sx cement. Shut in pressure 200 psi.

GPS: 38.75524 -100.50546

Perfs:

Top	Bot	Thru	Comments
3913	3914		
3892	3898		


INVOICED
OCT - 0 2017

Remarks: QES CEMENT TICKET # 49563

Plugged through: TBG

District: 04

Signed _____



(TECHNICIAN)

CM

KCC WICHITA

SEP 28 2017

RECEIVED

SEP 21 2017