

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-24027-00-00
Spot: SE Sec/Twnshp/Rge: 33-18S-21W
1466 feet from S Section Line, 1223 feet from E Section Line
Lease Name: RYERSEE Well #: 2-33
County: NESS Total Vertical Depth: 4259 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PC	5.5	1356		CEMENTED TO 390'
PROD	5.5	4258	0	WITH 280 SX CMT
SURF	8.625	230		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/13/2017 10:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (785) 398-2270

Proposed Plugging Method: TIE ONTO CASING & PUMP 35 SX CMT & 200# HULLS. SPACER TO 1400' THEN CMT TO SURFACE. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/13/2017 12:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMPED 50 SX CMT & 200# HULLS, THEN SPACER TO 1400' THEN 190 SX CMT. CMT DID NOT CIRCULATE, ON VACUUM. TIED ONTO BACKSIDE. PRESSURED RIGHT UP TO 300#. 9/19/17: TOC AT 700'. PUMPED 70 SX CMT. HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4254	4258		

INVOICED
OCT - 3 2017

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed

Michael Maier

(TECHNICIAN)

51A

RECEIVED
SEP 26 2017
KCC DODGE CITY