

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-03850-00-00  
Spot: S2SWNE Sec/Twnshp/Rge: 13-17S-11W  
2970 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: MEYERS B Well #: 4  
County: BARTON Total Vertical Depth: 3322 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	3305		125 SX
SURF	10	305		275 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/20/2017 11:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: KEVIN WILES SR Company: AMERICAN WARRIOR, INC. Phone: (620) 272-1023

Proposed Plugging Method: Ordered 225 sx 60/40 pozmix 4% gel cement, 275 sx common cement, 500 # hulls and 29 sx gel.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/20/2017 5:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Perforated at 1400', 600' and 300'. Ran tubing to 3200' and pumped 100 sx common cement w/3% cc. Pulled tubing to 2650' and pumped 19 sx gel. Pulled tubing to 1450' and pumped 8 sx gel followed by 50 sx common cement. Pulled tubing to 670' and pumped 80 sx common cement. Pulled tubing to 300'. Circulated cement to surface with 75 sx cement. Pulled tubing. Topped off with 5 sx cement. Tied to surface pipe and pumped 40 sx cement. Cement started pushing up casing.

09/21/2017 - Visually checked and plug is still full.

GPS: 38.57357 -098.48702

INVOICED  
LIST - 0 2017

Remarks: SWIFT SERVICES

Plugged through: TBG

District: 04

Signed

*Bruce Rodie*

(TECHNICIAN)

cm

KCC WICHITA

SEP 28 2017

RECEIVED

SEP 22 2017

Form CP-2/3