

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-053-21159-00-01
Spot: SWNWSESE Sec/Twnshp/Rge: 27-17S-10W
700 feet from S Section Line, 1170 feet from E Section Line
Lease Name: SCHEPMANN Well #: 2-27
County: ELLSWORTH Total Vertical Depth: 3410 feet

Operator License No.: 33770
Op Name: ARES ENERGY, LTD
Address: 405 N. MARIENFELD SUITE 250
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3275		
PROD	5.5	3406		225 SX
SURF	8.625	425		170 SX
T1	2.375	3353		

Well Type: OIL UIC Doc#et No: _____ Date/Time to Plug: 09/12/2017 9:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTER Company: ALLIANCE WELL SERVICE, INC. Phone: (620) 655-4494

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 09/12/2017 11:45 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, PULL RODS AND TUBING. SET CIBP @ 3275' AND CAP WITH 2 SX'S CEMENT. SHOOT OFF CASING AT 1310' AND PULL OUT OF HOLE. RUN TUBING TO 1300' AND PUMP 35 SX'S COMMON WITH 3% CC AND 100#'S COTTON HULLS. PULL TUBING TO 725' AND WAIT 1 HOUR. TAG CEMENT AT 1050'. RUN TUBING BACK DOWN TO 950' AND PUMP 35 SX'S COMMON WITH 3% CC. PULL TUBING TO 475' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3326	3341	CSG	
3322	3324		
3319	3326		
3318	3320		

INVOICED
09-12-17

Remarks: EXCEL WIRELINE - PRATT, KS. QUALITY OIL WELL CEMENT #403. TA NOV WELL.

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)