

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-053-21154-00-01  
Spot: W2SESWSE Sec/Twnshp/Rge: 27-17S-10W  
330 feet from S Section Line, 1715 feet from E Section Line  
Lease Name: SCHEPMANN Well #: 1-27  
County: ELLSWORTH Total Vertical Depth: 3430 feet

Operator License No.: 33770  
Op Name: ARES ENERGY, LTD  
Address: 405 N. MARIENFELD SUITE 250  
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3275		
PROD	5.5	3419		125 SX
SURF	8.625	465		240 SX
T1	2.375	3381		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/14/2017 9:00 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Revd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 655-4494

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 09/14/2017 12:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, PULL RODS AND TUBING. SET CIBP AT 3275' AND CAP WITH 2 SX'S CEMENT. SHOOT CASING OFF AT 1346' AND PULL OUT OF HOLE. RUN TUBING TO 1300' AND PUMP 35 SX'S COMMON WITH 3% CC AND 100# COTTON HULLS. PULL TUBING UP TO 750' AND WAIT 2 HOURS. TAG CEMENT AT APPROX. 1000'. RUN TUBING BACK DOWN TO 950' AND PUMP 35 SX'S COMMON WITH 3% CC, PULL TUBING TO 515' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3330	3338	CSG	
3320	3324		

INVOICED  
OCT - 3 2017

Remarks: EXCEL WIRELINE #1679. QUALITY OILWELL CEMENT #406. TA N.O.V. WELL.

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

15