

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-23952-01-00  
Spot: SWSWSESE Sec/Twnshp/Rge: 2-35S-10W  
208 feet from S Section Line, 1048 feet from E Section Line  
Lease Name: WILLIAM 3510 Well #: 2-11H  
County: BARBER Total Vertical Depth: 4805 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4750		WITH 50 SX CMT
COND	20	105		WITH 10 SX CMT
	L1 4.5	9639	0	WITH 315 SX CMT
PROD	7	5353	1765	WITH 275 SX CMT
SURF	9.625	918		WITH 650 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/25/2017 3:00 PM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Revd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 4750' WITH 50 SX CMT. PLUG AT 960' WITH 100 SX CMT. FILL TO 0' FROM 300'.

Plugging Proposal Received By: KEN SCOFIELD Witness Type: PARTIAL  
Date/Time Plugging Completed: 09/25/2017 6:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4750' WITH 50 SX CMT ON TOP OF CIBP THROUGH TBG. 1ST PLUG AT 960' WITH 100 SX CMT. 2ND PLUG AT 300' TO SURFACE WITH 100 SX CMT.

Perfs:

Top	Bot	Thru	Comments
8055	8484		
7522	7951		
6989	7418		
6460	6885		
5923	6352		
5390	5818		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES. TMD = 9639'

Plugged through: TBG

District: 01

RECEIVED  
SEP 29 2017  
KCC DODGE CITY

Signed Stephen J. Pfeifer  
(TECHNICIAN)  
51A