

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-23592-00-00  
Spot: SWNWSENE Sec/Twnshp/Rge: 22-34S-10W  
3327 feet from S Section Line, 996 feet from E Section Line  
Lease Name: KISLING Well #: 1  
County: BARBER Total Vertical Depth: 5358 feet

Operator License No.: 35053  
Op Name: TAPSTONE ENERGY, LLC  
Address: PO BOX 1608  
OKLAHOMA CITY, OK 73101

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4610		WITH 2 SX CMT
CIBP		5100		
PROD	4.5	5349	1000	WITH 255 SX CMT
SURF	10.75	230		WITH 230 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/15/2017 8:00 AM  
Plug Co. License No.: 35086 Plug Co. Name: SJL WELL SERVICE, LLC  
Proposal Rcvd. from: BOONE DAVIDSON Company: TAPSTONE ENERGY Phone: (405) 702-5480

Proposed Plugging Method: CIBP @ 4600' WITH 2 SX CMT. PLUG AT 620' WITH 12 SX GEL & 50 SX CMT. PLUG AT 270' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/15/2017 10:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4610' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 620' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 280' WITH 70 SX CMT. 3RD PLUG AT 60' WITH 50 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5112	5117		
4654	4672		

INVOICED  
OCT 12 2017

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC SERVICES.

Plugged through: TBG

District: 01

Signed

*Stephen J. Pfeifer*  
SJA

(TECHNICIAN)

RECEIVED  
SEP 25 2017  
KCC DODGE CITY